

Delta Industrial explains that

GETTING THE JOB DONE AHEAD OF SCHEDULE DOESN'T MEAN SACRIFICING SAFETY

April, 2018:

When Newman Technology, Inc. decided to add an 80,000 square foot addition to their current operating facility in 2017, they turned to the experts at Delta Industrial to install the building foundations and slab on grade. After a job well done, Delta was brought back to install foundations for Newman's new 400-ton, 600-ton, and 2000-ton presses. This was no easy feat. Delta had to work with varying subgrade soil conditions, while also tying into existing scrap tunnels. They drilled through soil/rock for H-pile and wood lagging earth retention, and utilized specialty equipment for the demolition and excavation of rock subgrade. Once shoring and excavation was complete, they safely and efficiently saw cut and removed existing scrap tunnel walls to tie in the new press foundations. During the construction process, they also installed and maintained a temporary air ventilation duct work system to protect the workers from any potential harmful fumes, debris, and dust. The end result? A project done ahead of schedule tailored to match existing foundations, centerlines, and scrap conveyor tunnels.



About Delta Industrial:

Delta Industrial is a "design-build" specialist, offering a variety of professional contracting services, including machine foundations, press pit foundations, slitting line foundations, general building maintenance & construction, concrete flatwork and steel fabrication & construction. With the diversity of construction knowledge that Delta brings to the job site, it quite simply **GUARANTEES** success in all facets of the project, regardless of the scope of work. From concept through design to finished product, Delta provides in-house services to accommodate all of your industrial contracting needs.